MYSORE PUBLIC WORKS DEPARTMENT.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received in the office of the Superintending Engineer, Cauvery Reservoir Works Division, up to 15th February 1916, for carting materials from Paschimavahini to Cauvery Reservoir Works (South Bank) and from French Rocks to dam site (North Bank).

2. The articles should be conveyed without delay as consignment are received by rail.

Further particulars and information required as to conditions may be had at the Superintending Engineer's Office at Cauvery Reservoir between the hours of 11 A.M. and 6 P.M. on any day except Sundays or other authorised holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200, two hundred in cash or promissory notes, as earnest money, and be superscribed "Tender for carting materials from Paschimavahini to Cauvery Reservoir Works (South Bank)," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Superintending Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be given separately for conveying heavy Machinery articles on trucks to be supplied by Government and for carting lighted articles in contractors own cart.

K. VENKATARAMAIYA,
For *Superintending Engineer,*
Cauvery Reservoir Works.

MYSORE DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th February 1916, for supply of all steel joists required for Taluk Cutcherry at Nanjangud. The supply should be completed by the end of April 1916, and the articles delivered at Nanjangud Railway Station.

2. Tenders should be submitted in the form noted below and be accompanied by statement in the form given below, showing the rates at per cwt. or ton.

FORM OF TENDER.

I hereby tender for the execution of all works necessary for
at the rates entered opposite to each item in the accompanying statement.

Dated

Description of work	Unit of work	Rate per unit

3. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for supply of steel joist for Taluk Cutcherry at Nanjangud."

4. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

List of rolled steel girders and joists required for the Taluk Cutcherry at Nanjangud.

Particulars	Weight per foot	Quantity required in number	Dimensions			Remarks
			L.	D.	Face	
Steel girders	Lb. 44	8	20′	12″	6″	
Do	,, 44	5	14½′	12″	6″	
Do	,, 18	1	15′	8″	4″	
Do	,, 18	1	9½′	8″	4″	
Steel Joists	,, 12	8	19½′			
Do	,, 12	5	11′			
Do	,,	4	26′			
Do	,,	1	20′			
Do	,,	1	15′			
Do	,,	1	14′	6″	3″	
Do	,, 12 lb.	4	22′			
Do	,, per	8	20′			
Do	,, foot.	4	28′			
Do	,,	4	24′			
Do	,,	6	27′			
Do	,,	6	19½′			

Y. ASVATHANARAYANA RAO,
Executive Engineer.

HASSAN DIVISION.

Dated 24th January 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to the 10th February 1916, for constructing Anglo-Vernacular School at Alur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1916.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 12 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred (Rs. 200) in cash or Government-Promissory Notes, as earnest money, and be superscribed "Tender for constructing Anglo-Vernacular School at Alur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity.
1	Earthwork excavating foundation	C. yd.	59
2	Burnt brick in mortar, foundation, basement and superstructure	C. ft.	3,104
3	Burnt brick in clay do	Do	3,182
4	Burnt stone slabs, dressed	S. ft.	485
5	Burnt brick in mortar, archwork	C. ft,	45
6	Teakwood pannelled door, with fastenings, lock, key, etc., complete	S. ft.	210
7	Do windows with iron bars, glazed and pannelled shutters, etc.	Do	254
8	Do work with oiling	C. ft.	163½
9	Roofing with 1st class Mangalore tiles, teak reepers, etc.	Sq.	84·5
10	Ridge tiles set in mortar and pointed	R. ft.	140
11	Zinc sheets for valleys	Do	192
12	Teakwood ¼″ planking do	Do	192
13	Chunam borders	Do	88
14	Teakwood eave board	Do	304
15	Chunam plastering	Sq.	79·50
16	White and colourwashing	Do	79·50
17	Flooring with Cuddapah slabs and Mangalore tiles over 3″ concrete and cement pointing	Do	20·43
18	Painting	Do	15·6
19	Tarring	Lump	sum.
20	Curving corners of rooms	Lump	sum.
21	Cutting grooves to pillars	No.	8
22	Mangalore ventilating tiles	Do	18
23	Clearing site, etc, ...	Lump	sum.
24	Constructing a latrine	Lump	sum.

K. R. SESHACHAR,
Executive Engineer.